

15-163-19294-00-00

Form GP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

9/30/63
SEP 30 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Frank Black
Complete Address: Box 150 Mc Pherson, Kansas
Lease Name Stuckey Well No. 4
Location CSW NE Sec. 32 Twp. 9 Rge. (E) (W) 18
County Rooks Total Depth 3699
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated: _____
Plugging Contractor: Knight Casing Pulling
Address: Chase, Kans License No. 436
Operation Completed: Hour 4PM Day 25 Month 9 Year 63

The Above well was plugged as follows:

8 5/8" 215' circulated with cement - 5 1/2" 3694' with 75 sax cement

Sand back to 3680', set 4 sax cement with dump bailer - pulled 2825'
5 1/2" to 590' - tried to circulate hole with heavy mud - hole pressured up-
pulled to 530' - tried to circulated - pulled to 470' and tried to
circulate - pulled to 410' tried to circulate - pulled to 350' tried
to circulate - pulled to 320' circulated hole with heavy mud - displaced
20 sax cement through 5 1/2" at 320' - heavy mud to 35' and cemented from
35' to bottom cellar.

Mudding and cementing by Knight Company Pump .

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/30/63

INV. NO. 7804-u

Signed: [Signature]
Well Plugging Supervisor