

15-163-19295-00-06

Form GP-3
Rev. 6-26-62

MO
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
10/8/63
OCT 8 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Frank Black
Complete Address: Box 150 Mc Pherson, Kansas
Lease Name Kuenster Well No. 1
Location CSE NW Sec. 32 Twp. 9 Rge. (E) (W) 18
County Rooks Total Depth 3700
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated: _____
Plugging Contractor: Knight Casing Pulling
Address: Chase, Kans License No. 436
Operation Completed: Hour 3PM Day 4 Month 10 Year 63

The Above well was plugged as follows:

8 5/8" 225' circulated with cement - 5 1/2" 3690' with 100 sax cement.

Filled with sand to 3660', set 4 sax cement with dump bailer - pulled 2416'
5 1/2" - tried to circulate with mud at 550' - hole pressured up - pulled
pipe to 362' - circulated hole with mud - used a total of 20 sax gel &
6 sax hulls - displaced 25 sax cement through 5 1/2" at 362' - heavy mud to
35' - cement 35' to bottom cellar.

Mudding and cementing by Knight Company Pump truck.

I hereby certify that the above well was plugged as herein stated.

DATE 10/10/63
INV. NO. 4858-W

Signed: Edon Leiby
Well Plugging Supervisor

INVOICED