

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
12/27/66  
DEC 27 1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Tomlinson-Kathol, Inc.,

Complete Address: 1125 Wichita Plaza Wichita, Kansas

Lease Name Richardson Well No. 3

Location S/2 NW SE Sec. 32 Twp. 9 Rge. 18 (E)    (W) X

County Rooks Total Depth 3689'

Abandoned Oil Well X Gas Well    Input Well    SWD Well    D & A   

Other well as hereafter indicated:   

Plugging Contractor: Knight Casing Pulling

Address: Chase, Kansas License No. 436

Operation Completed: Hour 1 P Day 17 Month 12 Year 1966

The Above well was plugged as follows:

Total Depth 3689' 8 5/8 csg set at 208' cwc.

5 1/2 csg set at 3685' cw 50 sc cement.

Sand back to 3670' and dumped 5 sc cement with dump bailer.

Recov. 3100' of 5 1/2 csg.

Squeezed thru 8 5/8 plug container with 25 sc gel mud and 75 sc cement.

Shut in pres. 150 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

12/27/66

NO. 4517-W

Signed: [Signature]  
Well Plugging Supervisor