

R

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: _____ Rooks

Location: NW SE SW Sec. 1 Twp. 9 Rge. 19 (E) (W)

Name of Field: _____ Total Depth: 3490

I have this date completed supervision of plugging of:

Lease Name: Gick Well No. 1

Operator's Full Name: Thunderbird Drg Co

Complete Address: 712 Union Center Wichita, Kans

Plugging Contractor: Southwest Casing Pulling Co & Globe Cementing Co

Address: Great Bend, Kans License No. 399

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 8 Month 3 Year 59

The above well was plugged as follows:

8 5/8" at 180' circulated with cement - 5 1/2" 3485' with 75 sax cement.
and squeezed at 1092' with 116 sax cement.

Filled with sand to 3470', set 4 sax cement with dump bailer, pulled
857' 5 1/2" to 600', circulated hole with heavy mud through 5 1/2" at 600',
(21 sax cel), displaced 20 sax cement through 5 1/2" at 600', heavy mud to
180', displaced 20 sax cement through 5 1/2" at 180', heavy mud to 35', set
bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Signed: Jedon L. Perry
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

PLUGGING
FILE SEC. 1 T. 9 R. 19w
BOOK PAGE 25 LINE 7

CONSERVATION DIVISION
Wichita, Kansas

4/16/59