

15-163-19043-00-00

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 67-44

LOCATION NW SE SW

SEC. 1 TWP. 9 RGE. 19

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Gick

Operator Lawrence Supply Co Address c/o West Supply Co Chase, Kans

Field _____ County Rooks

Total Depth 3460 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 200' circulated with cement - 5 1/2" at 3457' with

100 sax cement behind - Lane Wells plugs to 3215' - perforated
3192'.

Filled with sand to 3180', set 4 sax cement with dump bailer,

pulled 2620', 5 1/2" - filled with heavy mud to 200', set rock

and 15 sax cement, mud to 35', set rock and 10 sax cement to

bottom cellar.

Edson Lee
District Conservation Agent

Date 6-21-50

6/22/56

PLUGGING
FILE SEC. 1 T. 9 R. 19W
BOOK PAGE 67 LINE 44