

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 49-21
LOCATION S¹ SE NW
SEC. 1 TWP. 9 RGE. 19

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1-c Lease Slansky

Operator Continental Oil Co Address Box 481 Great Bend, Kans

Field _____ County Rooks

Total Depth 3465 Feet.

(Describe briefly the manner in which the well was plugged)

10 3/4" at 214' circulated with cement - 7" at 3459' with

200 sax cement behind - P. B. 3457' - perforated at 3186'.

Bridging plug at 3150', rock and 5 sax cement -

Pulled 2180' 7", filled with mud to 214', set rock and

20 sax cement - mud to 30', set rock and 10 sax cement to

bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
NOV 13 1952
CONSERVATION DIVISION
WICHITA, KANSAS

Edmond Petty

District Conservation Agent

Date 10-31-52

PLUGGING

FILE SEC 1 T 9 R 19
BOOK PAGE 49 LINE 21