

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20723-00-00
Spot: NW Sec/Twnshp/Rge: 6-28S-33W
3960 feet from S Section Line, 3960 feet from E Section Line
Lease Name: NELSON A GAS Well #: UT 1-6
County: HASKELL Total Vertical Depth: 2949 feet

Operator License No.: 31458
Op Name: HJ, INC.
Address: 70 N FARMLAND RD
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2947	0	WITH 580 SX CMT
SURF	8.625	925		WITH 450 SX CMT

95.84

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/05/2007 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed
Plugging
Method:

PUMP 400# HULLS & 25 SX CMT. GEL SPACER TO 930'. FILL CMT FROM 930' - 0'. CHECK BACKSIDE.

Plugging Proposal Received By: LINDLEY REIMER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/05/2007 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 400# HULLS & 25 SX CMT. PRESSURED TO 300#. PUMP 40 BBL MUD SPACER. PUMP 117 SX CMT FROM 950' TO 0'. PRESSURE TO 300#. PUMP 8 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS. PRESSURED TO 50#.

Perfs:

Top	Bot	Thru	Comments
2824	2832		
2774	2784		
2754	2764		

RECEIVED
KANSAS CORPORATION COMMISSION


NOV 29 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01



Signed

Ken Jehlik

(TECHNICIAN)

PT