

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-21184-00-00
Spot: SENWSW Sec/Twnshp/Rge: 14-6S-26W
1440 feet from S Section Line, 1030 feet from W Section Line
Lease Name: MOSS Well #: 14-2
County: SHERIDAN Total Vertical Depth: 3940 feet

Operator License No.: 33335
Op Name: IA OPERATING, INC.
Address: 9915 W 21ST ST, STE B
WICHITA, KS 67205

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	348		

128.05

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/14/2007 8:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: ANDY Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 190 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 11/14/2007 10:30 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

1st. Plug at 2215' w/25 sxs.
2nd. Plug at 1400' w/100 sxs.
3rd. Plug at 425' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 26 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

ND

Signed Case Morris
(TECHNICIAN)

PKT

NOV 19 2007