

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20148-00-00
Spot: NENW Sec/Twnshp/Rge: 19-20S-33W
660 feet from N Section Line, 1980 feet from W Section Line
Lease Name: CRIST R L - A Well #: 1
County: SCOTT Total Vertical Depth: 2795 feet

Operator License No.: 3045
Op Name: LANG, KENNETH R.
Address: 301 W BELLEVUE
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2794	677	WITH 325 SX CMT
SURF	8.625	365		WITH 150 SX CMT

90.84

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/16/2007 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/19/2007 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 20 SX CMT & 200# HULLS AT 2175'. (BRIDGE AT 2190'). FULL CIRCULATION. PULL 20 JTS TO 1550' & CIRCULATE HOLE WITH MUD. RAN BOND LOG FROM 1225' - 0'. TOC @ 740'. CONTAMINATED CMT TO 640'. TIH WITH TBG TO 1200'. SPOT 20 SX CMT. FULL CIRCULATION. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2717	2720		
2614	2626		

RECEIVED
KANSAS CORPORATION COMMISSION


NOV 29 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG

District: 0



Signed _____

Ken Jehlik
(TECHNICIAN)

PKS