

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-01016-00-01  
Spot: NWNWSE Sec/Twnshp/Rge: 32-24S-13W  
2610 feet from S Section Line, 2610 feet from E Section Line  
Lease Name: GLASSCOCK A Well #: 1  
County: STAFFORD Total Vertical Depth: 4305 feet

Operator License No.: 31980  
Op Name: LOTUS OPERATING COMPANY, L.L.C.  
Address: 100 S MAIN STE 420  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3670		WITH 2 SX CMT
PROD	5.5	4267	1593	WITH 220 SX CMT
SURF	8.625	250		WITH 175 SX CMT

13a. a1

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/02/2007 9:00 AM  
Plug Co. License No.: 33645 Plug Co. Name: PLAINS, LLC  
Proposal Rcvd. from: ROBIN BROWN Company: LOTUS OPERATING Phone: (620) 546-4801

Proposed Plugging Method: CIBP @ 3670' & 2 SX CMT. PLUG AT 860' WITH 15 SX GEL - 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/02/2007 12:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

\*\*JUNK IN HOLE: TBG & PACKER. TOP OF FISH @ 3711'\*\* SET CIBP @ 3670' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LAID DOWN CASING & RUN TBG TO PLUG THROUGH. 1ST PLUG AT 860' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4004	4056		MISS

RECEIVED  
KANSAS CORPORATION COMMISSION


NOV 29 2007

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed

*Stephen J Pfeifer*  
(TECHNICIAN)

PKT