

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-21454-00-00
Spot: NENENE Sec/Twnshp/Rge: 14-34S-36W
4950 feet from S Section Line, 330 feet from E Section Line
Lease Name: WEST GREGG Well #: 1-14
County: STEVENS Total Vertical Depth: 6700 feet

Operator License No.: 30421
Op Name: N.L.S., INC.
Address: 3981 JOE BALD RD
KIMBERLING CITY, MO 65686

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	6391	1880	WITH 555 SX CMT
SURF	8.625	1750		WITH 800 SX CMT

21775

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/30/2007 10:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: SAND BACK TO 6190' & 5 SX CMT. PLUG AT 1770' WITH 50 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: LINDLEY REIMER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/31/2007 10:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 25 SX CMT & 300# HULLS TO 6250'. PRESSURE TO 500#. 1ST PLUG AT 1780' WITH 50 SX CMT. 2ND PLUG AT 660' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6242	6250		

RECEIVED
KANSAS CORPORATION COMMISSION


NOV 29 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED CLASS A CMT BY SARGENTS.

Plugged through: CSG

District: 01



Signed _____

Ken Jehlik

(TECHNICIAN)

PKY
AS