

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-23124-00-00
Spot: N2NESW Sec/Twnshp/Rge: 19-30S-11W
2310 feet from S Section Line, 3300 feet from E Section Line
Lease Name: LAVERENTZ Well #: 1-19
County: BARBER Total Vertical Depth: 4575 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4574	3600	WITH 125 SX CMT
SURF	8.625	434		WITH 175 SX CMT

148.69

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/26/2007 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND BACK TO 4400' & 4 SX CMT. PLUG AT 1200' WITH 50 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: PARTIAL
Date/Time Plugging Completed: 11/26/2007 12:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4400' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 1200' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 450' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4458	4461		

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 29 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

District: 01

RECEIVED
NOV 27 2007
KCC Dodge City

Signed Stephen J. Pfeifer
(TECHNICIAN)