

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21775-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 19-33S-31W
4450 feet from S Section Line, 4349 feet from E Section Line
Lease Name: SANDERS Well #: 1-19
County: SEWARD Total Vertical Depth: 2720 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2719	0	WITH 400 SX CMT
SURF	8.625	553		WITH 300 SX CMT

86' 40"

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/22/2007 10:00 AM
Plug Co. License No.: 32453 Plug Co. Name: ACID SERVICES LLC
Proposal Rcvd. from: DAVE HAYES Company: OIL PRODUCERS Phone: (316) 682-3022

Proposed Plugging Method: PUMP 25 SX CMT & 100# HULLS AT 1000'. CIRCULATE CMT FROM 600' TO SURFACE. CHECK ANNULUS.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/22/2007 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

RODS & TBG IN WELL. TOP OF FISH @ 1100'. PUMP 25 SX CMT & 275# HULLS AT 998'. PUMP 40 SX CMT THROUGH TUBING AT 595'. LOST CIRCULATION THEN GOT PARTIAL RETURNS. TOO H WITH TUBING. WAIT 2 HOURS. TAG TOP OF CMT IN 4 1/2" @ 187'. FLUID LEVEL AT 90'. TIH WITH TBG TO 155' & CIRCULATE CMT TO SURFACE WITH 40 SX CLASS A CMT. TOO H WITH TUBING. PUMP 150 SX CLASS A CMT DOWN ANNULUS AT 200#. SHUT IN PRESSURE 150#. (4 1/2" CASING FILLED UP FROM 40' TO 4' WHILE PUMPING DOWN ANNULUS.)

Perfs:

Top	Bot	Thru	Comments
2647	2653		
2587	2610		
2551	2566		
2517	2530		

RECEIVED
KANSAS CORPORATION COMMISSION


NOV 29 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL & CLASS A CMT BY BASIC ENERGY.

Plugged through: TBG

District: 01



Signed

Ken Jehlik

(TECHNICIAN)

Form C-143

PKT