

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-20067-00-00
Spot: SWNW Sec/Twnshp/Rge: 35-8S-29W
3325 feet from S Section Line, 4767 feet from E Section Line
Lease Name: PRATT Well #: 1
County: SHERIDAN Total Vertical Depth: 4215 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4214	0	200 SX
SURF	8.625	220	0	165 SX

136.99

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/09/2007 1:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: GARY REH Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 470 sxs 60/40 pozmix - 4% gel - 750# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/09/2007 4:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 220' w/165 sxs cement.
5 1/2" production casing set at 4214' w/200 sxs.
PBTD 4117'. TD 4215'.
Cement squeezes: 2045'-2105' w/200 sxs; 2052'-2082' w/135 sxs.
Ran tubing to 2500' - pumped 240 sxs cement with 2% cc and 600# hulls.
Pulled tubing to 1500' - pumped 75 sxs cement. Cement to surface.
Pulled tubing to surface. Connected to 5 1/2" production casing - pumped 40 sxs cement.
Max. P.S.I. 250#. S.I.P. 0#.
Connected to 8 5/8" surface casing - pumped 35 sxs cement.
Max. P.S.I. 350#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3919	4104		
3307	3345		

INVOICED

DATE 11-28-07
INV. NO. 2008060812

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 16 2007

CONSERVATION DIVISION
WICHITA KS

Remarks: SWIFT SERVICES CEMENT COMPANY-TICKET #13113.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

PKT

35-8-29W
C SW NW

ROCK ISLAND OIL & REF., CO. #1 PRATT

Contr. RED TIGER DRLC

Cty. SHER DAN

Geol.

Pool HOXIE WEST DISC.

E. 2826 RB Cm. 12/25/57 Cp. 3/21/58 IP LANS 3919-4104 &
126 BOPD, NW
API 15-179-20, 057
HOW 3807-45

LOG TOPS	Depth	Datum
* ANHY	2134	1492
HOW	3584	759
HEEL	3878	1052
TOP	3902	1076
LANS	3917	1091
R.K.C.	4152	1355
ID	4215	1389

Csgs. 8" 218/155 SX, 5 1/4" 193
 DST 3543-3600/30", 1360' OIL & MDY OIL, BHP
 1118-1110#/30", FP 36-555#
 DST 3602-3073' 51' 0", 60' OCM, 60' SLI WM,
 BHP 1070-906#/30", FP 32-72#
 DST 3646-3710/21' 30" 0, 60' MO, 300' OCMW
 BHP 1170-1116#/30", FP 54-561#
 DST 3713-45/21', 2050' SW/SPKS OIL, BHP 1143-
 1143#/30", FP 63-979#
 DST 3761-85/11', 1644' OIL, 30' WTR, 2HP
 1198-1143#/30", FP 72-698#
 DST 3804-30/11', 2060' OIL, 31' MO, BHP 1207-
 1180#/30", FP 63-824#
 DST 3832-70/11', G/55", 3390' CO, 15' MDY
 FRESH W, BHP 1207-1207#/30", FP 126-1161#
 DST 3870-3910/11', G/64", 2830' CO, 45' DM,
 BHP 1211-1216#/30", FP 163-1015#

* SMP
 INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

(CONT'D)