

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-20076-00-01
Spot: SENWNW Sec/Twnshp/Rge: 35-8S-29W
4307 feet from S Section Line, 4577 feet from E Section Line
Lease Name: PRATT HOXIE Well #: 3
County: SHERIDAN Total Vertical Depth: 4220 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4219	0	225 SX
SURF	8.625	222	0	180 SX
T1	2.375	3787		

137.15

Well Type: EOR UIC Docket No: E18370.2 Date/Time to Plug: 11/12/2007 1:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (316) 263-3535

Proposed Plugging Method: Ordered 345 sxs 60/40 pozmix - 4% gel - 600# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 11/12/2007 4:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 222' w/180 sxs cement.
4 1/2" production casing set at 4219' w/225 sxs cement.
PBSD 4193'. TD 4220'.
Cement squeezes: from 1700' w/350 sxs and 750' w/200 sxs.
Ran tubing to 2500' - pumped 200 sxs cement with 300# hulls.
Pulled tubing to 1500' - pumped 50 sxs cement. Cement to surface.
Pulled tubing to surface. Connected to 4 1/2" production casing - pumped 20 sxs cement.
Max. P.S.I. 250#. S.I.P. 0#.
Connected to 8 5/8" surface casing - pumped 1/4 sack cement.
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
4104	4107		
4064	4068		
3998	4002		
3910	3914		
3848	3854		

INVOICED
DATE 11-28-07
INV. NO. 2008060812

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 16 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: SWIFT SERVICES CEMENT COMPANY-TICKET #12956.

Plugged through: TBG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

NOV 14 2007

PKT

ROCK ISLAND OIL & REF. CO. INC. #3 PRATT 35-8-29W
SE NW NW

Contr. RED TIGER DRLG City. SHERIDAN

Geol. Pool HOXIE WEST

E. 2825 KB Cm. 2/22/68 Cp. 3/21/68 IP P 120 BOPD, NW
LANS 4104-07

API 15-179-20,076

LOG Tops	Depth	Datum	Csg. 8" 222/180 SX, 4" 4220
ANHY	2439	+ 386	DST 3652-70/31, 30' GSY OIL, 60'
HEEB	3887	-1062	OGMSW, 120' SW, BHP 1206--
IQR	3909	-1084	1008#/30", FP 21-116#
LANS	3924	-1099	DST 3894-3920/2', 2225' SW, BHP
BKC	4166	-1341	1248-1227#/30", FP 63-1060#
RID	4220	-1395	DST 4045-65/2', 1680' GIP, 300'
			OIL, 120' OCM, 1530' SW, BHP
			1311-1311#/30", FP 52-903#
			DST 4070-4120/2', 2200' GIP, 920'
			GSY OIL, 360' HO&SCM, NW,
			BHP 1351-1342#/30", FP 35-434#
			CO PF 12/4104-07, A 800, REC LD,
			SMB 10 BOPH, NW/4 HRS, POP.

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS