

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-20432-00-00
Spot: SENWSWNW Sec/Twnshp/Rge: 35-8S-29W
3431 feet from S Section Line, 4844 feet from E Section Line
Lease Name: PRATT Well #: 4
County: SHERIDAN Total Vertical Depth: 4150 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4152	0	200 SX
SURF	8.625	218	0	185 SX

134.88

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/08/2007 1:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (316) 263-3535

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 600# hulls.
Plug thru tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/08/2007 4:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 218' w/185 sxs cement.
5 1/2" production casing set at 4150' w/200 sxs cement.
PBTD 4117'. TD 4150'.
Cement squeezes: 2085'-2113' w/150 sxs; 2099'-2129' w/150 sxs; 2140'-2180' w/200 sxs;
2260'-2780' w/200 sxs; 2568'-2600' w/150 sxs; 2873'-2902' w/200 sxs.
Ran tubing to 2500' - pumped 175 sxs cement with 400# hulls.
Pulled tubing to 1600' - pumped 150 sxs cement with 150# hulls.
Pulled tubing to 800' - pumped 30 sxs cement - cement to surface.
Pulled tubing to surface. Connected to 5 1/2" production casing - pumped 10 sxs cement.
Max. P.S.I. 300#. S.I.P. 0#.
Connected to 8 5/8" surface casing - pumped 35 sxs cement.
Max. P.S.I. 250#. S.I.P. 0#.

Perfs:

Top	Bot	Thru	Comments
3766	3769		
3593	3595		
3584	3588		

INVOICED

DATE 11-28-07
INV. NO. 2008060812

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 16 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: SWIFT SERVICES CEMENT COMPANY-TICKET#12982.

Plugged through: TBG

District: 04

DD Signed Darrel Dipman
(TECHNICIAN)

PKT

