

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-19021-00-01
Spot: NWNENE Sec/Twnshp/Rge: 25-11S-21W
4950 feet from S Section Line, 990 feet from E Section Line
Lease Name: HUCK Well #: 1
County: TREGO Total Vertical Depth: 1403 feet

Operator License No.: 5893
Op Name: PRATT WELL SERVICE, INC.
Address: PO BOX 847
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1403	0	w/200 sxs cmt

45.60

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 11/14/2007 8:00 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: DARRELL ENSILEY Company: PRATT WELL SERVICE, INC. Phone: (620) 770-0995

Proposed Plugging Method: Ordered 100 sxs 60/40 pozmix - 4% gel.
CIPB set at 1000' with one sack cement set 10/18/1974.
Was Huck #1 SWD Docket D-08151.
10/27/1974 was converted to water supply well identified as Dakota Supply Well.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/14/2007 10:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs: _____
RIH with 1" tubing to 826' - tagged junk in the hole - pulled one joint to 800'.
Rigged to 1" tubing and pumped 50 sxs 60/40 pozmix - 4% gel to circulate cement to surface.
Pulled tubing - rigged to 4 1/2" casing with a swedge and pumped 5 sxs cement with 100# P.I.P.
Blew small hole in casing near surface - cement circulating up around head.

INVOICED
DATE 11-28-07
INV. NO. 2008060815


RECEIVED
KANSAS CORPORATION COMMISSION
NOV 16 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #26070.

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

NOV 14 2007

PRT