

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-21005-00-00  
Spot: NWSENW Sec/Twnshp/Rge: 31-25S-5E  
3624 feet from S Section Line, 3715 feet from E Section Line  
Lease Name: APPLEMAN A Well #: 5  
County: BUTLER Total Vertical Depth: 2540 feet

Operator License No.: 32693  
Op Name: HAWKINS OIL, LLC  
Address: 427 S BOSTON AVE STE 915  
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2539		50 SX CMT
SURF	8.625	197		85 SX CMT <u>82.55</u>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/16/2007 8:00 AM  
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C  
Proposal Rcvd. from: JIM BRADEN Company: BRADEN PETROLEUM & PLUGGIN Phone: (620) 222-1252

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 01/19/2007 12:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

01-16-2007 MIRU, SANDED BACK @ 2430', DUMP BAILED 4 SXS CEMENT ON TOP OF SAND. 01-18-2007 SHOT 4-1/2" CSG @ 1580', LAYED DOWN W/45 JTS. 4-1/2" CSG. 1-19-2007, RIH W/TBG @ 250', BRADEN MIXED & PUMPED 100 SXS 60/40 POZMIX 4% GEL TO SURFACE, P.A. COMPLETE 1230 1-19-2007. BRADEN PETROELUM TICKET #07-552. 1-23-2007 TAGGED TOP PLUG @ 80'. 11-1-2007, TOP OFF WELL, RIH W/TBG @ 70', BRADEN PETROELUM & WELL PLUGGING MIXED & PUMPED 32 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET #07-605.

Perfs:

Top	Bot	Thru	Comments
2484	2486		

**INVOICED**  
DATE 11-28-07  
INV. NO. 2008060799

RECEIVED  
KANSAS CORPORATION COMMISSION

Remarks: -096.92618,37,83466, PERFS 2484'-2486', PBDT 2515'

Plugged through: TBG

NOV 15 2007

CONSERVATION DIVISION  
WICHITA, KS

District: 02

Signed

Duane Krueger

(TECHNICIAN)

PCT