

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-22598-00-00
Spot: W2NWNENW Sec/Twnshp/Rge: 1-26S-4E
4981 feet from S Section Line, 3818 feet from E Section Line
Lease Name: PORTER D Well #: 1A
County: BUTLER Total Vertical Depth: 2511 feet

Operator License No.: 32693
Op Name: HAWKINS OIL, LLC
Address: 427 S BOSTON AVE STE 915
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2066		
PROD	4.5	2509		180 SX CMT
SURF	8.625	225		140 SX CMT

81.61

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/23/2007 8:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C
Proposal Rcvd. from: JIM BRADEN Company: BRADEN PETROLEUM & WELL PL Phone: (620) 222-1252

Proposed Plugging Method: AS PER KCC RULES & REGS SAND TO 1950' W/4 SXS, PULL PIPE & CIRCULATE TOP PLUG FROM 275'

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 11/01/2007 4:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

10-23-2007, SANDED BACK @ 1930', DUMP BAILED 4 SXS CEMENT ON TOP. 10-26-2007, PARTED PIPE @ 1127', LAYED DOWN 28 JTS 4-1/2" CASING (1127'). 11-1-2007, RIH W/TBG @ 275'. BRADEN PETROLEUM & WELL PLUGGING MIXED & PUMPED 110 SXS 60/40 POZMIX 4% GEL TO SURFACE. P.A. COMPLETE 1600 PM 11-1-2007. CEMENT CIRCULATED. BRADEN PETROLEUM & WELL PLUGGING TICKET #07-604

Perfs:

Top	Bot	Thru	Comments
2420	2433		
2000	2017		

INVOICED
DATE 11-28-07
INV. NO. 2008060799

RECEIVED
KANSAS CORPORATION COMMISSION


NOV 15 2007

Remarks: -096.94771,37.82380 CIBP @ 2066'. PERFS 2000'-2017'

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

PKT