

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-079-00333-00-01  
Spot: NWNWSW Sec/Twnshp/Rge: 35-24S-2E  
2236 feet from S Section Line, 4975 feet from E Section Line  
Lease Name: EILERT Well #: 8  
County: HARVEY Total Vertical Depth: 2862 feet

Operator License No.: 30742  
Op Name: PALOMINO PETROLEUM, INC.  
Address: 4924 SE 84TH ST  
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2842		
SURF	8	207		

93.02

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/24/2007 10:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: ED NEMNICH / JOE STRUB Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: SAND TO 2,790' & TOP WITH 4 SKS. CEMENT. CIRCULATE CEMENT FROM 260' TO THE SURFACE.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: PARTIAL  
Date/Time Plugging Completed: 09/24/2007 10:00 AM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

SANDED TO 2,790' & TOPPED WITH 4 SXS, CEMENT. PERFORATED 4 1/2" CASING @ 260'. RAN 1" TUBING TO 270' CIRCULATED 140 SXS. CEMENT TO THE SURFACE INSIDE 4 1/2" CASING & IN 8 5/8" X 4 1/2" ANNULUS.

Perfs:

INVOICED  
DATE 11/28/07  
INV. NO. 2008660801

Remarks: USED 60/40 POSMIX W/4% GEL BY COPELAND ACID & CEMENT. INVOICE #32577.

Plugged through: TBG

RECEIVED  
KANSAS CORPORATION COMMISSION

NOV 15 2007

CONSERVATION DIVISION  
WICHITA, KS

District: 02

Signed Michael Wilson  
(TECHNICIAN)