

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-00343-00-00
Spot: SENWSW Sec/Twnshp/Rge: 35-24S-2E
1643 feet from S Section Line, 4387 feet from E Section Line
Lease Name: EILERT Well #: 7
County: HARVEY Total Vertical Depth: 2857 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2865		
SURF	8	129		

92.85

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/01/2007 11:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: ED NEMNICH / JOE STRUB Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: Sand to 2,790' & top with 5 sxs. cement. Circulate cement from 250' to the surface.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: PARTIAL
Date/Time Plugging Completed: 10/01/2007 12:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

SANDED TO 2,790' & TOPPED WITH 5 SXS. CEMENT. PERFORATED 5 1/2" CASING @ 250'. RAN 2 3/8" TUBING TO 270' & CIRCULATED 90 SXS. CEMENT TO THE SURFACE INSIDE 5 1/2" CASING & 8 5/8" X 5 1/2" ANNULUS. 10/05/07 - CHECKED TOP PLUG - CEMENT DOWN 40' INSIDE 5 1/2" CASING - NOTIFIED OPERATOR. 11/06/07 - RAN 1" IN 5 1/2" TUBING TO 40' & CIRCULATED 10 SXS. CEMENT TO THE SURFACE.

Perfs:

INVOICED
DATE 11-28-07
INV. NO. 2008060801

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 15 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY COPELAND ACID & CEMENT. INVOICE #32425 & #32252.

Plugged through: TBG

District: 02

Signed

Michael Wilson

(TECHNICIAN)

PKT