

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-20656-00-00
Spot: SENESW Sec/Twnshp/Rge: 35-24S-2E
1650 feet from S Section Line, 3024 feet from E Section Line
Lease Name: FAITH Well #: 13
County: HARVEY Total Vertical Depth: 3703 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3433	1658	160sx
SURF	8.625	201		115sx
T1	2.875	3395		

120.35

Well Type: SWD UIC Docket No: D27958.0 Date/Time to Plug: 10/01/2007 8:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: ED NEMNICH / JOE STRUB Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: SAND TO 2,790' & TOP WITH 5 SXS. CEMENT. CIRCULATE CEMENT FROM 255' TO THE SURFACE.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: PARTIAL
Date/Time Plugging Completed: 10/01/2007 11:00 AM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

SANDED TO 2,790' & TOPPED WITH 5 SXS. CEMENT. RIPPED 5 1/2" CASING @ 1,620'. PULLED CASING TO 220' & CIRCULATED 120 SXS. CEMENT TO THE SURFACE. 10/05/07 CHECKED TOP PLUG - CEMENT DOWN 90' - NOTIFIED OPERATOR. 11/07/07 RAN 1" TUBING TO 90' & CIRCULATED 30 SXS. CEMENT TO THE SURFACE.

Perfs:

INVOICED
DATE 11-28-07
INV. NO. 2008060801

Remarks: USED 60/40 POSMIX W/4% GEL BY COPELAND ACID & CEMENT. INVOICE #32424 & #32252.

Plugged through: CSG

District: 02

Signed Michael Wilson
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 15 2007

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

PKT