

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-23670-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 24-27S-5E
3002 feet from S Section Line, 2268 feet from E Section Line
Lease Name: ULLUM Well #: 24-01
County: BUTLER Total Vertical Depth: 2800 feet

Operator License No.: 33639
Op Name: ULLUM, CHARLES O. DBA ULLUM OIL
Address: 9333 SE TURKEY CRK RD
LEON, KS 67074

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2800		135 SX
SURF	8.625	281		160 SX

91.00

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/17/2007 8:00 AM
Plug Co. License No.: 9576 Plug Co. Name: WHITEMAN, RON DBA GEN-DOR OIL CO.
Proposal Rcvd. from: DAVE CORNISH Company: CORNISH OIL COMPANY Phone: (316) 259-7048

Proposed Plugging Method: SAND 50' ABOVE KC PERF & 5 SX CEMENT, REC, PIPE, CIRC CEMTN 330'-0'

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE
Date/Time Plugging Completed: 10/29/2007 11:30 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 2212', DUMP BAILED 5 SXS CEMENT ON TOP. SHOT 5-1/2" CSG @ 1900', 1711', 1500', & 1290', LAYED DOWN 31 JTS 5-1/2" CSG (1290'). 10-29-2007, RIH W/TBG @ 335', UNITED CEMENTING MIXED & PUMPED 160 SXS 60/40 POZMIX 4% GEL TO SURFACE. P.A. COMPLETE 11:30 AM 10-29-2007. CEMENT CIRCULATED. UNITED CEMENTING TICKET #8082.

Perfs:

Top	Bot	Thru	Comments
2750	2754		
2350			
2262	2266		

INVOICED
DATE 11-28-07
INV. NO. 2008060802

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: -096.83341.37.68758, BP @ 2350', PERFS 2262'-2266'

Plugged through: TBG

NOV 15 2007

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed Duane Krueger
(TECHNICIAN)

PKT