

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-20263-00-02
Spot: NWNWSW Sec/Twnshp/Rge: 28-25S-5E
2006 feet from S Section Line, 4777 feet from E Section Line
Lease Name: BURLINGAME STOKES A Well #: 71
County: BUTLER Total Vertical Depth: 2560 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2285		25 SX
DVT		1317		
PROD	5.5	2559		300 SX
SURF	8.625	94		90 SX

83.20

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/05/2007 8:00 AM
Plug Co. License No.: 30437 Plug Co. Name: UNITED CEMENTING AND ACID CO., INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORP. Phone: (316) 655-1997

Proposed Plugging Method: PER KCC RULES & REGS, 25 SXS @ 935'. CIRC FULL @ 250', 1" BACKSIDE FROM 40' TO SURFACE

Plugging Proposal Received By: GREG EVES Witness Type: NONE
Date/Time Plugging Completed: 10/05/2007 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

DV TOOL @ 1317' W/450 SXS, TOC - 40' SIMPSON 2488'-2504'. RETAINER 2483', VIOLA 2467'-2479', CIBP @ 2285', 647'-654', 50 SX CEMENT, 532'-544' 100 SXS CEMENT, KC 2011'-2061' TO SXS, LECOMPTON 1280'-1284' 35 SXS, 10-5-2007, RIH W/TBG @ 935', UNITED CEMENTING MIXED & PUMPED 25 SXS CLASS A 2% CC. WAITED 2-HOURS, TAGGED CEMENT @ 760', RIH W/TBG @ 250', UNITED CEMENTING MIXED & PUMPED 35 SXS CLASS 2% CC TO SURFACE. TOPPED OFF BACKSIDE FROM 40' TO SURFACE. CEMENT CIRCULATED, UNITED CEMENTING TICKET #8058. P.A. COMPLETE 1700 10-5-2007.

Perfs:

Top	Bot	Thru	Comments
2488	2504		SIMPSON
2467	2479		VIOLA
2059	2061		KC
2029	2033		KC
2011	2016		KC
1280	1284		LECMP
647	659		ADMIRE
530	544		ADMIRE

INVOICED

DATE

11-28-07

INV. NO.

2008060803

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: -096.89318,37.84469

Plugged through: TBG

NOV 15 2007

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

Duane Krueger

(TECHNICIAN)

P167