

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23347-00-00
Spot: W2SWSENW Sec/Twnshp/Rge: 20-10S-20W
3020 feet from S Section Line, 3780 feet from E Section Line
Lease/Unit Name: HELEN KELLER Well Number: 1
County: ROOKS Total Vertical Depth: 3815 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 4514 COLE AVE., STE 804, LB 30
DALLAS, TX 75205

Conductor Pipe: Size feet: 123.99
Surface Casing: Size 8.625 feet: 237
Production: Size feet:
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 07/03/2002 5:00 AM
Plug Co. License No.: 9431 Plug Co. Name: VONFELDT DRILLING, INC
Proposal Rcvd. from: DOUG BUDIG Company: VONFELDT DRILLING, INC Phone: (785) 483-6446

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 07/03/2002 8:00 AM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 1700' w/25 sxs. Anhydrite 1658' - 1702'.
2nd. Plug at 960' w/100 sxs. Dakota 584' - 884'.
3rd. Plug at 290' w/40 sxs. Surface pipe to 237'.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

RECEIVED
AUG 22 2002
08-22-2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 8-22-02

INV. NO. 2003060346

AUG 21 2002