

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20240-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 2-4S-19W
4290 feet from S Section Line, 4950 feet from E Section Line
Lease Name: GRAU A Well #: G-2
County: PHILLIPS Total Vertical Depth: 3444 feet

Operator License No.: 31569
Op Name: BACH, JASON DBA BACH OIL PRODUC
Address: PO BOX 723
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3444	0	275 SX
SURF	8.625	207	0	150 SX

111.93

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/01/2007 9:00 AM
Plug Co. License No.: 31569 Plug Co. Name: BACH, JASON DBA BACH OIL PRODUCTION
Proposal Rcvd. from: BACH OIL PRODUCTION Company: BACH, JASON DBA BACH OIL PRO Phone: (785) 476-5254

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/01/2007 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 1570' - pumped 100 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pulled tubing to 700' - pumped 100 sxs 60/40 pozmix - 4% gel with 200# hulls with 500# to 600#. - pressured to circulate.
Pulled all tubing - pumped 25 sxs 60/40 pozmix - 4% gel.
S.I.P. 500#.
Pumped 25 sxs 60/40 pozmix - 4% gel down backside.
S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3242	3381		

RECEIVED
NOV 19 2007
KCC WICHITA

INVOICED

Remarks: ALLIED CEMENTING COMPANY-TICKET #24782.

Plugged through: TBG

DATE 11-30-07
INV. NO. 2008060822

District: 04

Signed Pat Bedore PIRT I
(TECHNICIAN)

NOV 07 2007

[Handwritten signature]

AMERICAN PETROLEUM CO., INC. 2-4-19W
 SUITE 111, 400 NO. WOODLAWN #G-2A GRAU SW NW NW
 WICHITA, KS. 67208
 CONTR TORNADO DRLG. CTV PHILLIPS

GEOL BILL PETERSEN FIELD BECKMAN EAST CONE

E 2051 KB CM 8/18/78 CARD ISSUED 10/19/78 IP P 84 BOPD N/W
 LKC 3288-3381

+	+	+
+	+	+
+	+	+

API 15-147-20,240

LOG	TOPS	DEPTH	DATUM
-B FT HAYS		288	+1763
ANH		1537	+ 514
B ANH		1573	+ 478
TOP		2964	- 913
HEEB		3165	-1114
TOR		3188	-1137
LANS		3207	-1156
B KC		3426	-1375
TD		3446	-1395

8-5/8" 207/150 sx, 4 1/2" 3444/275 SX
 NO DST
 MICT - CO, PF 3371-81, AC 1250, PF
 3336-40, AC 500, PF 3288-92, AC 2500,
 PF 3260-64, 3242-46, AC 8000, REC LD,
 POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS