

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20444-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 27-19S-33W
2970 feet from S Section Line, 2310 feet from E Section Line
Lease Name: SMITH G Well #: 2
County: SCOTT Total Vertical Depth: 4760 feet

Operator License No.: 3045
Op Name: LANG, KENNETH R.
Address: 301 W BELLEVUE
GARDEN CITY, KS 67846

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| PC | | 2265 | | WITH 425 SX CMT |
| PROD | 4.5 | 4759 | 0 | WITH 200 SX CMT |
| SURF | 8.625 | 381 | | WITH 205 SX CMT |

154.70

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/08/2007 10:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 200# HULLS & 20 SX CMT ON BOTTOM. MUD BACK TO 1350'. 100 SX CMT TO SURFACE DOWN 4 1/2". CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL
Date/Time Plugging Completed: 11/09/2007 12:00 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

PORT COLLAR @ 2265' WITH 425 SX CMT. PUMP 200# HULLS & 20 SX CMT AT 4250'. MUD SPACER TO 1350'. 1ST PLUG AT 1350' WITH 77 SX CMT. 2ND PLUG PULL TO 300' & PUMP 23 SX CMT. NO RETURNS. PUMP 9 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS. 11/9/07: TOP OF CEMENT AT 350'. PUMPED 26 SX CMT. PRESSURED TO 500#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4408 | 4412 | | |
| 4303 | 4313 | | |


INVOICED
DATE 11-30-07
INV. NO. 2008060827

RECEIVED
NOV 19 2007
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG

District: 01



Signed

Jerry W. Stapleton
PIRTEH
(TECHNICIAN)

PIRTEH