

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-29667-00-00
Spot: NWSWSESW Sec/Twnshp/Rge: 5-24S-19E
495 feet from S Section Line, 1485 feet from W Section Line
Lease Name: THOOHOFF Well #: 5
County: ALLEN Total Vertical Depth: 1016 feet

Operator License No.: 30370
Op Name: RICKERSON, RUSSELL
Address: 4252 JOHN BROWN RD
RANTOUL, KS 66079

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	21	0	

35.00

Well Type: Oil DH KCC PRT UIC Docket No: _____ Date/Time to Plug: 11/12/2007 4:00 PM
Plug Co. License No.: 33977 Plug Co. Name: E K ENERGY LLC
Proposal Revd. from: DALE KIMSEY Company: E.K. ENERGY LLC Phone: (620) 496-6257

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASSED BORE TO 1016'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT T.D., A 50' CEMENT PLUG AT 500', AND TO PLACE A CONTINUOUS CEMENT PLUG FROM 200' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE
Date/Time Plugging Completed: 11/12/2007 6:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE WELL TO T.D.. 10 SACKS OF CEMENT WERE PUMPED THROUGH THE 1" PIPE TO T.D.. THE PIPE WAS PULLED TO 500' AND 10 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE 1" PIPE WAS PULLED TO 200'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

RECEIVED
KCC DISTRICT #3

NOV 15 2007 CPT

CHANUTE, KS

INVOICED
DATE 11-30-07
INV. NO. 2008060830

RECEIVED
NOV 19 2007
KCC WICHITA

Remarks: SPOT LOCATION WAS ESTABLISHED VIA GPS AS 501' NSL & 3838' WEL OF S.5.

Plugged through: TBG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

PRT