

5-17 15-163-19368-00-01

6 020531

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 10-9-56  
NW NE NW , SEC. 35 , T 10 S, R 20 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 6931

Operator: Bowman Oil Co.  
Name & Address: Box 17  
Codell, Ks. 67630

4950 feet from S section line  
3630 feet from E section line  
Lease Name Armbrister Well # A-1  
County Rooks 122.69  
Well Total Depth 3775 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 195' w/150 sks

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ U&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Bowman Oil Co. License Number 6931  
Address Same

Company to plug at: Hour: 10:00AM Day: 17 Month: May Year: 19 90

Plugging proposal received from Don Bowman

(company name) Bowman Oil Co. (phone) \_\_\_\_\_

were: 5 1/2 set at 3770 w/200 sks. Perf 3625 - 31; 3538 - 44; 3529 - 34.  
5 1/2 was sq 977 - 1166' w/200 sks (1/9/74).

Shot three holes in 5 1/2" at 1530'. There is a hole in dakota.

Plugging Proposal Received by Gilbert Balthazor (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:45PM Day: 17 Month: May Year: 19 90

ACTUAL PLUGGING REPORT Ran tubing to 2200'. Pumped 50 sks 60/40 poz 8%

gel followed w/50 sks common cement. Pulled tubing to 1100' and cir cement 105  
sks to surface 60/40 poz 8% gel w/700 lbs. hulls. Pumped down 5 1/2" casing.  
85 sks 60/40 poz 8% w/200 lbs. hulls. Pumped down annulus 60 sks cement 60/40  
poz 8% gel and 100 lbs. hulls. Max pres on annulus 400 lbs. Shut in 200 lbs.  
Max pres on 5 1/2 800 lbs. Shut in 300 lbs.

Remarks: By Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED 1990  
do not observe this plugging.

DATE 5-30-90  
INV. NO. 28283  
JUL 1 1 1990

Signed Gilbert Balthazor (TECHNICIAN)  
Gilbert Balthazor