

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21454-00-00
Spot: NWSENE Sec/Twnshp/Rge: 9-31S-16W
1520 feet from N Section Line, 875 feet from E Section Line
Lease Name: HASHKNIFE Well #: 1-9
County: COMANCHE Total Vertical Depth: 4965 feet

Operator License No.: 31021
Op Name: CASTELLI EXPLORATION, INC.
Address: 6908 W 112TH
OKLAHOMA CITY, OK 73162

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	24	65		
PROD	4.5	4964	3250	WITH 150 SX CMT
SURF	13.38	308		WITH 290 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/14/2007 3:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DALLAS PRESTON Company: CASTELLI EXPLORATION Phone: (620) 886-0612

Proposed Plugging Method: PUMP 30 SX CMT & 200# HULLS ON BOTTOM. PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. PLUG AT 320' WITH 80 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 11/14/2007 5:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMPED 200# HULLS & 30 SX CMT TO BOTTOM. 1ST PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 320' WITH 80 SX CMT. 3RD PLUG AT 40' WITH 40 SX CMT. 11/15/07: TOPPED OFF WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4917	4932		
4895	4899		

RECEIVED
KANSAS CORPORATION COMMISSION


NOV 29 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY CEMENTING.

Plugged through: CSG

District: 01



Signed

Michael Maier
(TECHNICIAN)

Form CP-233