

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20080-00-00
Spot: NWNE Sec/Twnshp/Rge: 32-32S-29W
4620 feet from S Section Line, 1980 feet from E Section Line
Lease Name: ROBERTS Well #: 1
County: MEADE Total Vertical Depth: 5794 feet

Operator License No.: 4951
Op Name: CLAASSEN OIL AND GAS, INC.
Address: PO BOX 417
ESTES PARK, CO 80517

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5460		WITH 2 SX CMT
PROD	5.5	5790	2535	WITH 125 SX CMT
SURF	8.625	1466		WITH 750 SX CMT

168.31

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/15/2007 12:00 PM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULLI Phone: (580) 254-1881

Proposed Plugging Method: CIBP @ 5460' & 2 SX CMT. PLUG AT 1470' WITH 50 SX CMT. PLUG AT 690' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE
Date/Time Plugging Completed: 11/15/2007 4:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

CIBP @ 5460' & 2 SX CMT. 1ST PLUG AT 1470' WITH 50 SX CMT. 2ND PLUG AT 690' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5691	5696		
5646	5650		
5614	5620		

RECEIVED
KANSAS CORPORATION COMMISSION


NOV 26 2007

Remarks: USED COMMON CMT BY SARGENT & LILLARD.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: CSG

District: 01



Signed

Steve Durrant
(TECHNICIAN)

per