

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23817-00-01

Spot: NENWNW

Sec/Twnshp/Rge: 29-14S-19W

4943 feet from S Section Line, 4360 feet from E Section Line

Lease Name: GABEL

Well #: 1-29

County: ELLIS

Total Vertical Depth: 3710 feet

Operator License No.: 30961

Op Name: A P S, INC.

Address: 750 MT PLEASANT RD
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3681	0	175 SX
SURF	8.625	504	0	400 SX

120.58

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/08/2007 8:30 AM

Plug Co. License No.: 99996

Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: WILFRED T. BARNES

Company: A.P.S., INC.

Phone: (785) 625-5361

Proposed
Plugging
Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 500# hulls - 15 sxs gel.
720' tubing in the hole at 2942'.
PF LK at 3466'. PBTB 3681'. Low fluids.

Plugging Proposal Received By: PAT STAAB

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/08/2007 11:30 AM

KCC Agent: PAT STAAB

Actual Plugging Report:

Allied rigged to 5 1/2" casing with a swedge - pumped 35 sxs 60/40 pozmix - 4% gel with 100# hulls, followed with 15 sxs gel with 200# hulls, followed with 200 sxs 60/40 pozmix and 200# hulls.
Max. P.S.I. 1000#. S.I.P. 1000#.
Cut hole in 8 5/8". Backside full of cement.

Perfs:

INVOICED
DATE 11-15-07
INV. NO. 200 8060769

RECEIVED
NOV 13 2007


KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET#33274.

Plugged through: CSG

District: 04

Signed


(TECHNICIAN)

NOV 08 2007

PAT

STATE: KANSAS COUNTY: ELLIS 29-14S-19W
FIELD: ETHEL
OPER: CHALLENGER EXPL
WELL: 1-29 GABEL
API: 15-051-23817-0001
SPUD: 04/27/93
DTD: 3710 LTD: FTD: ARBUCKLE
WELL CLASS: DO
STATUS: OIL-WO
COMP: 05/11/93
330 FNL 990 FWL SEC
ELEV: 2168 GR
P8TD: 3690

LOC: 3 MI NW ANTONINO, KS

IP: COMP 5/11/93, IPP 6 BO, 10 BWPO, GTY 32 PROD ZONE- LANSING-KANSAS CITY
3650-3662

SPL TOPS:

LANSING-KANSAS CITY	3466 -1298	
TD	3710 -1542	

NO LOGS RUN

CSGS: 8 5/8 @ 504 W/400 SX, 5 1/2 @ 3681 W/175 SX; TBG: 2 3/8 @ 3685; DRLG COMP
04/28/93 RIG REL 04/28/93

OWWO: OWWO: OLD INFO: FORMERLY R&R EXPL 1-29 GABEL SPUD 3/5/84. OTD 3800.
COMP 9/26/84. OIL WELL PROD ZONE: FM & INT NOT RPTD. NEW INFO: TO DO &
TEST ARBUCKLE.

PRODUCING INTERVAL: PERF (LANSING-KANSAS CITY)

COPYRIGHT 1993 PETROLEUM INFORMATION CORPORATION
(OVER)

DATE 06/18/93 CARD # 000006-KS