

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-20281-00-01  
Spot: NWNW Sec/Twnshp/Rge: 11-11S-22W  
4620 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: KRAMER OWWO Well #: 1  
County: TREGO Total Vertical Depth: 3920 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3919	0	200 SX CMT
SURF	8.625	218	0	175 SX CMT

127.40

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/06/2007 11:00 AM  
Plug Co. License No.: 33137 Plug Co. Name: GASCHLER WELL SERVICE LLC  
Proposal Rcvd. from: DICK SCHREMMER Company: BEAR PETROLEUM, INC. Phone: (316) 524-1225

Proposed Plugging Method: Ordered 255 sxs 60/40 pozmix - 4% gel - 500# hulls.  
DV Tool at 1700' w/350 sxs. CIBP at 3850'. Squeeze at 3544' - 3745'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/06/2007 2:25 PM KCC Agent: PAT STAAB

Actual Plugging Report:  
RIH with tubing to 3501'. Rigged to tubing and pumped 50 sxs with 150# hulls mixed in.  
Pulled tubing to 3000'. Rigged to tubing and pumped 8 sxs gel followed with 5 sxs gel and 100# hulls mixed in, followed with 10 sxs 60/40 pozmix - 4% gel.  
Pulled tubing to 1500'. Rigged to tubing and pumped 150 sxs cement with 250# hulls mixed in to circulate cement to surface.  
Pulled tubing. Rigged to 4 1/2" casing and pumped 20 sxs cement.  
Max. P.S.I. 300#. S.I.P. 300#.  
Rigged to 8 5/8" - pumped 25 sxs cement.  
Max. P.S.I. 150#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3794	3814		

INVOICED

DATE 11-15-07  
INV. NO. 2008060770

RECEIVED  
NOV 13 2007  
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #C-32250.

Plugged through: TBG

District: 04

Signed   
(TECHNICIAN)

NOV 07 2007

*PS*

REPLACEMENT CARD

DAMAR RESOURCES  
 P. O. BOX 70  
 HAYS, KS 67601

CONTR #1 KRAMER "OWMO"  
 ABERCROMBIE DRILLING

CITY TREGO

11-11-22W  
 C. NW NW

GEOLOGICAL FIELD DEMURRY EXT (1/4 S)

ELV 2200 KB SPD 11/8/83 CARD ISSUED 2/24/84 # P 60 BOPD. NW  
 MARM 3794-3814

+	+	+
+	+	+
+	+	+

LOG	Tops	Depth-Depth
*SC	.....	1662 + 538
HEEB	.....	3438-1238
LANS	.....	3478-1278
BKC	.....	3719-1519
MARM	.....	NOT AVAILABLE
CONG CHT	.....	3840-1640
REW ARB	.....	3848-1648
ARB	.....	3856-1656
ORTD	.....	3900-1700
OLTD	.....	3902-1702
DOTD	.....	3920-1720
*DRILLERS TOP		

API 15-195-20, 281-A

OLD INFO: OPERATOR WAS F & M OIL COMPANY, INC., #1 KRAEMER, SPD 6/2/74, SET 8 5/8 - 218 / 175SX, COMP AS D&A/ DRILLING ARB 6/9/74 (CARD ISSUED 6/13/74), CONTR: ABERCROMBIE DST (1) 3643-3730 (LKC) / 30-30-30-30, REC 20' M, SIP 86-86#, FP 63-71# DST (2) 3852-70 (REW ARB) / 30-30-30-30, REC 30' M, SIP 55-47#, FP 38-38# NEW INFO: RE-ENTERED 11/8/83, WSH DWN TO OTD, DD 3820 TD, SET 4 1/2 " 3919/200SX, MICT - CO, PF (MARM) 3794-3814, FRAC'D (AMTS NA), SWB DWN, GSO, POP, P 60 BOPD, NW, 2/22/84

INFO RELEASED: 8/16/84 - WAS TIGHT HOLE

COPYRIGHT 1984  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS