

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-20262-00-00
Spot: SW Sec/Twnshp/Rge: 27-21S-37W
1320 feet from S Section Line, 1320 feet from W Section Line
Lease Name: GOERING Well #: 1
County: KEARNY Total Vertical Depth: 3091 feet

Operator License No.: 5317
Op Name: FREEMAN, RUSSELL DBA CONTINENT
Address: PO BOX 918
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1160		
CIBP		2276		WITH 2 SX CMT
CIBP		2964		
PROD	4.5	3088	0	WITH 180 SX CMT
SURF	8.625	307		WITH 250 SX CMT

100.46

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/23/2007 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: GREG BERNACKI Company: CONTINENTAL ENERGY Phone: (620) 276-8710

Proposed Plugging Method: SET CIBP @ 2880' & 2 SX CMT. TEST 4 1/2" CASING TO 300-500#. PEFORATE 4 1/2" @ 1150'. ATTEMPT TO CIRCULATE CMT FROM 1150' TO 0'. IF CANNOT ESTABLISH CIRCULATE PUMP CASING COLUME PLUS 80 SX CMT OUT PERFS. HOOK UP TO 8 5/8" X 4 1/2" ANNULUS & PUMP 200 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/23/2007 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2276' WITH 2 SX CMT. COULD NOT GET ANY DEEPER. CIBP @ 1160'. TEST 4 1/2" CASING TO 600# & HELD. PERFORATED AT 1150'. PUMP 80 SX CMT, 200# HULLS, & 70 SX CMT THROUGH PERFS. PRESSURE DECREASED TO 100 PSI, THEN INCREASED TO 800 PSI WITH HULLS & PERFS. HOLDING 550#. HAD NO BLOW OR CIRCULATION UP ANNULUS. PUMP 200 SX CMT DOWN 4 1/2" X 8 5/8" ANNULUS AT 200 TO 350 PSI. HELD AT 200#.

Perfs:

Top	Bot	Thru	Comments
2902	2964		

INVOICED
DATE 11-15-07
INV. NO. 2008060774

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 13 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01
RECEIVED
OCT 26 2007
KCC Dodge City

Signed Ken Jehlik
(TECHNICIAN)