

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-19183-00-01
Spot: SWSW Sec/Twnshp/Rge: 26-17S-9W
660 feet from S Section Line, 3960 feet from E Section Line
Lease Name: OGDEN Well #: 4
County: ELLSWORTH Total Vertical Depth: 3643 feet

Operator License No.: 7757
Op Name: FOLK, MAX LEE DBA FOLK OIL
Address: 205 N COUNTY RD
HOLYROOD, KS 67450

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3170		
SURF	10.38	211		

118.40

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/24/2007 3:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE INC. Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 10/24/2007 5:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

ATTEMPT TO RUN TUBING TO BOTTOM- ENCOUNTERED WHAT APPEARED TO BE SOLID BLOCKAGE @ 1160'. ATTEMPTED TO GET THRU-COULD NOT. PERFORATED CASING @ 1160', 800' AND 260'. RUN TUBING TO 1160' AND PUMPED 15 SX'S GEL FOLLOWED BY 50 SX'S CEMENT. PULL TUBING TO 800' AND PUMP 50 SX'S CEMENT. PULL TUBIN TO 260' AND CIRCULATE CEMENT TO SURFACE. USED 245 SX'S TOTAL CEMENT. TOPPED OFF ON 10-31-2007 WITH 5 SX'S DOWN 7" CASING & 10 SX'S ON BACKSIDE.

INVOICED
DATE 11-15-07
INV. NO. 2008060777

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 13 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ 4% GEL. COPELAND TICKET #C32173 AND #32546. LOG TECH 5118

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

PVT