

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22370-00-01
Spot: SENWNW Sec/Twnshp/Rge: 32-20S-7W
4140 feet from S Section Line, 4400 feet from E Section Line
Lease Name: DAVIS Well #: 1
County: RICE Total Vertical Depth: 3353 feet

Operator License No.: 31980
Op Name: LOTUS OPERATING COMPANY, L.L.C.
Address: 100 S MAIN STE 420
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3330		100 SX
SURF	8.625	207		210 SX

108.97

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/07/2007 7:45 AM
Plug Co. License No.: 33645 Plug Co. Name: PLAINS, LLC
Proposal Rcvd. from: ROBIN BROWN Company: LOTUS OPERATING CO. Phone: (620) 546-4801

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/07/2007 9:45 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SET CIBP @ 3175' AND CAP WITH 2 SX'S CEMENT, CUT OFF CASING @ 2007' AND PULL OUT OF HOLE. RUN TUBING BACK DOWN TO 1050' AND PUMP 35 SX'S CEMENT, PULL TUBING TO 600' AND PUMP 35 SX'S CEMENT, PULL TUBING TO 260' AND CIRCULATE CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3225	3350		

INVOICED

DATE 11-15-07
INV. NO. 2008060780

RECEIVED
KANSAS CORPORATION & C
NOV 13 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4%GEL. ALLIED TICKET #30979

Plugged through: TBG

District: 02

Signed _____

Virgil Clothier
(TECHNICIAN)

PWT