

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21679-00-00
Spot: E2SWNW Sec/Twnshp/Rge: 17-13S-26W
1840 feet from N Section Line, 930 feet from W Section Line
Lease Name: FOSSETT Well #: 1
County: GOVE Total Vertical Depth: 4450 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	224		

144.63

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/01/2007 6:00 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: FRANK ROME Company: PALOMINO PETROLEUM, INC. Phone: (316) 799-1000

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB
Date/Time Plugging Completed: 11/01/2007 9:00 AM

Witness Type: NONE
KCC Agent: PAT STAAB

Actual Plugging Report:

1st. Plug at 2080' w/25 sxs.
2nd. Plug at 1097' w/100 sxs.
3rd. Plug at 274' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

INVOICED
DATE 11-15-07
INV. NO. 2008060783

RECEIVED
NOV 13 2007
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

(TECHNICIAN)

NOV 08 2007