

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21280-00-00
Spot: NWSW Sec/Twnshp/Rge: 21-19S-9W
1980 feet from S Section Line, 4620 feet from E Section Line
Lease Name: R L LINK Well #: 1
County: RICE Total Vertical Depth: 3314 feet

Operator License No.: 30364
Op Name: RESOURCE OPERATIONS, INC.
Address: BOX 9487
TULSA, OK 74157

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3312		175 SX CMT.
SURF	8.625	241		175 SX CMT.

107.71

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/26/2007 1:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 10/26/2007 5:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

RUN TUBING TO 3200' AND PUMP 40 SX'S CEMENT WITH 200#'S COTTON HULLS AFTER PERFORATING AT 1200', 800' AND 290'. PULL TUBING TO 1200' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 800' AND PUMP 35 SX'S CEMENT PULL TUBING TO 290' AND CIRCULATE CEMENT TO SURFACE. USED 175 SX'S CEMENT. TOPPED OFF ON 10-31-2007- 1YD CEMENT. TICKET #44708

Perfs:

Top	Bot	Thru	Comments
3133	3137		
3099	3104		
2966	2976		

INVOICED
DATE 11-15-07
INV. NO. 2008060786

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 13 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET C32174. LOG TECH 5126

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

PVT