

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21042-00-00
Spot: W2NENE Sec/Twnshp/Rge: 15-29S-18W
660 feet from N Section Line, 760 feet from E Section Line
Lease Name: DARGEL TRUST Well #: 1
County: KIOWA Total Vertical Depth: 4980 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 155 N MARKET STE 700
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4978	2470	WITH 200 SX CMT
SURF	8.625	521		WITH 300 SX CMT <u>161.85</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/02/2007 12:50 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: PAT LIVINGSTON Company: VINCENT OIL Phone: (620) 546-3316

Proposed Plugging Method: SANDED BACK TO 4800' & 5 SX CMT OR SET CIBP @ 3460' & 2 SX CMT. PLUG AT 1135' WITH 15 SX GEL & 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/02/2005 2:25 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SAND TO 4800' WITH 5 SX CMT. 1ST PLUG AT 1135' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 550' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. GOOD RETURNS, CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4862	4872		
3506	3510		


INVOICED
DATE 11-15-07
INV. NO. 2008060787

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 13 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 01



Signed Eric MacLaren
(TECHNICIAN)