

6 030863

API NUMBER 15- 163-22,911-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

E/2 SW SE SEC. 17, T 10 S, R 20 W/E

660' feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4668

Lease Name Thomason Well # 1

Operator: Seville Drilling Corp.

County Rooks 122.79

Name & Address P.O. Box 668

Well Total Depth 3778 feet

La. Crosse, Ks. 67548

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 250'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Western Kansas Drilling Inc. License Number 4083

Address Hays, Kansas

Company to plug at: Hour: PM Day: 24 Month: 1 Year: 19 87

Plugging proposal received from Frank Taggart

(company name) Western Kansas Drilling Inc. (phone) _____

were: Order 215 sks 60/40 pozmix-6% gel - 3% cal. Cl. 1 sk hulls and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss. Balance plugs with mud. Allied Cement Co.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:15 PM Day: 24 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT

1st. plug 3825' w/25 sks

2nd plug 1710' w/25 sks

3rd plug 950' w/100 sks plus 1 sx hulls

4th plug 300' w/40 sks

5th plug 40' w/10 sks plus wiper plug

Remarks: 15 sks in rat hole, Anhy 1709', Elev. 2228

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-22-87

INV. NO. 16623

MAY 14 1987

STATE CORPORATION COMMISSION

APR 22 1987

CONSERVATION DIVISION
Wichita, Kansas

Signed

Carl Goodrow (TECHNICIAN)

Carl Goodrow