

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05079-00-00
Spot: SENWNE Sec/Twnshp/Rge: 25-11S-18W
4290 feet from S Section Line, 1650 feet from E Section Line
Lease Name: MARSHALL Well #: 11
County: ELLIS Total Vertical Depth: 3605 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY, A GENERAL
Address: 805 CODELL RD
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3605	0	w/150 sxs cmt
SURF	8.625	1235	0	w/525 sxs cmt

117.16

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/13/2007 11:00 AM
Plug Co. License No.: 6931 Plug Co. Name: BOWMAN OIL COMPANY, A GENERAL PARTNERSHIP
Proposal Rcvd. from: LOUIS "DON" BOWMAN Company: BOWMAN OIL COMPANY, A GENE Phone: (785) 434-2286

Proposed Plugging Method: Ordered 425 sxs 60/40 pozmix - 4% gel - 800# hulls - 15 sxs gel.
Perf at 1825' - 1260' - 700'. Well perf at 3521' to 3527'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/13/2007 6:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3503' - stacked out - pumped 15 sxs gel with 40 sxs cement and 100# hulls.
Pulled tubing to 1825' - pumped 85 sxs cement with 500# hulls.
Pulled tubing to 900' - pumped 200 sxs cement with 250# hulls.
Pulled tubing - topped off with 30 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3521	3527		

INVOICED


DATE 11-28-07
INV. NO. 2008060804

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 16 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #24802.

Plugged through: TBG

District: 04

Signed 
(TECHNICIAN)

NOV 14 2007




ICEP BROTHERS #11 MARSHALL 25-11-18W
SE NW NE
 Contr. ISERN DRILG CO ELLIS County
 E 1977RB Comm. 9-20-57 IP 25 BOPD

Tops	Depth	Datum
HEEB	3165	-1188
KG	3210	-1233
CONG	3165	-1188
SIMP DOL	3195	-1518
ARB	3515	-1538
TD	3605	-1628

Casing
 8" 1235
 5" 3605
 PERF 3521-27: 4 BOPH/8 HRS

BEMIS SHUTTS POOL



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS