

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Vincent Oil Corporation
Address: 155 N Market, Suite 700, Wichita, KS 67202
Phone: (316) 262-3573 Operator License #: 5004
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Steve Durrant (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Stotler Depth to Top: 3563 Bottom: 3570 T.D. 3651
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 097-21443-0000
Lease Name: Koehn
Well Number: 1-24
Spot Location (QQQQ): S/2 - SE - NW -
2225 Feet from North / South Section Line
1970 Feet from East / West Section Line
Sec. 24 Twp. 29 S. R. 19 East West
County: Kiowa
Date Well Completed: 9-25-99
Plugging Commenced: 11-6-07
Plugging Completed: 11-8-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	365	0
				4 1/2	3651	2420

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 3510', bailed 4 sacks cement, set floor, pulled slips, had 17" stretch, ripped casing at 2630', worked pipe, ripped casing at 2470', worked pipe free, pulled casing up to 1260', pumped 15 gel, 50 sacks at 1260', pulled to 400', pumped 50 sacks, pulled to 40', pumped 20 sacks to surface.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925 RECEIVED KANSAS CORPORATION COMMISSION

Address: 190 US Highway 56, Ellinwood, KS 67526

NOV 20 2007

Name of Party Responsible for Plugging Fees: Vincent Oil Corporation

State of KANSAS County, SEDGWICK, ss.

CONSERVATION DIVISION
WICHITA, KS


Richard A. Hiebsch (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Richard A. Hiebsch

(Address) 155 N. Market, Suite 700, Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 19th day of November 2007

Yolanda Eubanks My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]

QUALITY OILWELL CEMENTING, INC.

Phone 785-483-2025
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 1500

Date 11-8-07	Sec. 24	Twp. 29	Range 19	Called Out	On Location	Job Start 9:00	Finish 11:00
Lease Keeha		Well No. 1-27		Location 85 1/2 W of Greensburg		K.owa County KS State	

Contractor Quality Well	Owner Vincent
Type Job Plug	To Quality Oilwell Cementing, Inc. You are hereby requested to rent cementing equipment and furnish cementer or helper to assist owner or contractor to do work as listed.

Hole Size	T.D.	Charge To Vincent oil Corp.
Csg. 4 1/2	Depth	Street
Tbg. Size	Depth	City
Drill Pipe	Depth	State
Tool	Depth	The above was done to satisfaction and supervision of owner agent or contractor
Cement Left in Csg.	Shoe Joint	
Press Max.	Minimum	
Meas Line	Displace	

CEMENT

EQUIPMENT			Amount Ordered 120 SKS 60/40 4% Gel
			Consisting of
Pumptrk 6	No. 1	Cementer Helper Dave	Common 72 @ 11.00
Bulktrk 3	No. 1	Driver Rich	Poz. Mix 48 @ 6.00
Bulktrk	No. 1	Driver Dean	Gel. 15 gel. 20 @ 17.00
			Chloride
			Hulls

JOB SERVICES & REMARKS			
Pumptrk Charge PTA	700.00	4 1/2 whipper plug	52.00
Mileage 41 @ 6.00	246.00		
Footage			
Total			946.00

Remarks:			Sales Tax
1st	15 gel 50SKS. at 1260	Handling 140 @ 1.90	266.00
2nd	50SKS at 400	Mileage 8¢ per sk per mile	459.20
3rd	20SKS at 40' to surface.	PUMP TRUCK CHARGE	946.00
			Sub Total
			Total

Floating Equipment & Plugs	
Squeeze Manifold	RECEIVED
Rotating Head	KANSAS CORPORATION COMMISSION
	NOV 20 2007
	CONSERVATION DIVISION
	WICHITA, KS

Tax 198.17	
Discount (315.00)	
Total Charge 3,028.7	

X Signature **David Brady**