

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH


X

Locate well correctly on above  
Section Plat

Rooks County. Sec. 17 Twp. 10 Rge. 20 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE SE SW  
Lease Owner Mallonee Drilling Company, Inc., etal  
Lease Name Desbien Well No. 2  
Office Address 812 Central Bldg., Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed Sept. 8, 1953  
Application for plugging filed " " 19 "  
Application for plugging approved " " 19 "  
Plugging commenced " " 19 "  
Plugging completed " " 19 "  
Reason for abandonment of well or producing formation No producing formation.

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3873 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	223'	Circulated set at 210' to surface

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud to 200', pumped through drill pipe. Wood plug at 200'.  
15 sks mixed cement on plug.  
Mud to 40', pumped through drill pipe. Wood plug at 40'.  
10 sks mixed cement on plug.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mallonee Drilling Company, Inc.  
Address 812 Central Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
F. W. Mallonee (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) F. W. Mallonee

09-181953 812 Central Bldg., Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of September, 19 53

F. E. Mallonee  
Notary Public.

My commission expires March 7, 1957



15-163-00561-00-00

DRILLER'S LOG

#1 DESBIEN

SE SE SW SEC. 17-10S-20W

ROOKS COUNTY, KANSAS

OPERATOR: I. O. Miller  
CONTRACTOR: Mallonee Drilling Company, Inc.  
COMMENCED: 8-26-53  
COMPLETED: 9-8-53

ELEV: 2203 R.B.  
D & A

<u>FROM</u>	<u>TO</u>	<u>DESCRIPTION</u>	<u>REMARKS</u>
0 -	40	Shale	
40 -	120	Sand and shale	
120 -	210	Shale	8-5/8 casing set at 210' with 135 sks and 1 CC
210 -	260	Shale	
260 -	650	Shale and shells	
650 -	1080	Shale and sand	
1080 -	1200	Shale	
1200 -	1430	Sand	
1430 -	1698	Shale	
1698 -	1743	Anhydrite	
1743 -	1750	Shale	
1750 -	2065	Shale and shells	
2065 -	2485	Lime and shale	
2485 -	2675	Lime	
2675 -	3285	Lime and shale	
3285 -	3455	Lime	
3455 -	3480	Lime and shale	
3480 -	3710	Lime	
3710 -	3755	Lime and shale	
3755 -	3835	Chert	
	3873	Total Depth of Hole	

TOPS

Heebner	3458	(-1255)
Toronto	3479	(-1276)
Lansing	3496	(-1293)
Base K.C.	3718	(-1515)
Shaley Conglomerate	3782	(-1579)
Cherty Conglomerate	3820	(-1617)
Total Depth	3873	(-1670)

I certify that to the best of my knowledge and belief the above represents a true and accurate Driller's Log record of the above captioned well.

*R. E. Mallonee*

R. E. Mallonee

09-18-1953

