

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Ken L. Cody
Address: 1125 Road 27 Longton, Ks. 67352
Phone: (620) 642-6123 Operator License #: 7786
Type of Well: Gas D&A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: October 30, 2006 (Date)
by: KCC- Wichita (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Depth to Top: 1568 Bottom: 1609 T.D. 1609
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-049-22.081-0000
Lease Name: Cody
Well Number: Cody # 2
Spot Location (QQQQ): NW - SE - NW - NW
4400 Feet from North / South Section Line
4560 Feet from East / West Section Line
Sec. 13 Twp. 30 S. R. 12 East West
County: ELK
Date Well Completed: 4-27-89
Plugging Commenced: 10-15-07
Plugging Completed: 10-15-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
436 to 476	Water	40'	Surface	7"	40'	none
		1609	Surface	4 1/2"	1609	none
1568 to 1609	Gas & Water					

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

100' Cement Plug From 1609' to 1509' -- Gel From 1509' to 760' -- Cement Plug From 760' to 710' -- Gel to 350' -- Cement Plug From 350' to Surface. Cemented Through 2" Tubing To Spot Plugs.

Name of Plugging Contractor: ELMORE'S INC. License #: 32884 RECEIVED KANSAS CORPORATION COMMISSION
Address: Box 87-776, Highway 99, Sedan, Kansas - 67361 NOV 14 2007
Name of Party Responsible for Plugging Fees: Ken L. Cody CONSERVATION DIVISION WICHITA, KS
State of Kansas County, ELK, ss.

RAY EBBERTS (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Ray Ebberts, Agent
(Address) 3342 SW Friar Rd. Topeka, Ks. 66614

SUBSCRIBED and SWORN TO before me this 13th day of November, 2007

 **Stephanie Bales**
Notary Public
State of Kansas

Stephanie Bales My Commission Expires: 2-1-2009
Notary Public

My Appt. Expires 2-1-2009 Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten signature]

STATEMENT

7600

ELMORE'S INC.
 Box 87 - 776 HWY99
 Sedan, KS 67361
 Cell: (620) 249-2519
 Eve: (620) 725-5538

Date
 10-15-07

Customer Ken Cooby
 Address _____
 City _____ State _____ Zip _____

Qty.	Description	Price	Amount
50	SKS Cement	7.75	387.50
4	hr Cement Pump	80.00	320.00
4	hr Water Truck	70.00	280.00
1	Bank Tank	60.00	60.00
2	SKS Coel	12.00	24.00
			1071.50
	Plug Job 4 1/2"	tax	62.50
		\$	1134.00
	Cemented Thru 2" Tubing		
	1550' Mixed 10 BBL Coel		
	Water Spotted 10 SKS At		
	1550' Pulled Up To 7'60'		
	Spotted 5SK Cement Pulled		
	Up To 350' Cemented To		
	Surface With 35 SKS.		

Thank You -- We appreciate your business!

Rec'd. by _____

TERMS: Account due upon receipt of services. A 1 1/2% Service Charge, which is an annual percentage rate of 18% will be charged to accounts after 30 days.

RECEIVED
 KANSAS CORPORATION COMMISSION

NOV 14 2007

CONSERVATION DIVISION
 WICHITA KS