

AFFIDAVIT OF COMPLETION FORM

ACO-1

This form shall be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, **(SWD)**, OWWO, injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316)263-3238.

OPERATOR LIBERTY ENTERPRISES, INC.

API NO. 15-163-21,405-00-00

ADDRESS 308 West Mill

COUNTY Rooks

Plainville, Kansas 67663

FIELD Webster Field

**CONTACT PERSON Charles G. Comeau

PROD. FORMATION Granite Wash SWDW

PHONE 913-434-4686

LEASE McClellan

PURCHASER _____

WELL NO. #2

ADDRESS _____

WELL LOCATION NW SE SE

DRILLING CONTRACTOR PIONEER DRILLING COMPANY, INC.

990 Ft. from South Line and

ADDRESS 308 West Mill


990 Ft. from East Line of

Plainville, Kansas 67663

the SE/4 SEC. 4 TWP. 9S RGE. 19W

PLUGGING CONTRACTOR _____

ADDRESS _____



WELL PLAT

KCC
 KGS
 MISC
 (Office Use)

TOTAL DEPTH 3619' PBTD _____

SPUD DATE 9/10/81 DATE COMPLETED 11/27/81

ELEV: GR 2021' DF 2024' KB 2026'

DRILLED WITH ~~CONCRETE~~ (ROTARY) ~~TOOLS~~ TOOLS

(New) / ~~(Used)~~ casing.

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	20#	249'	Common	140	2% gel, 3% cc
Production	7 7/8"	5 1/2"	14#	3514'	50-50 poz	350	6% gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Pecker set at
2 7/8	3000'	3000'

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

RECEIVED
 STATE CORPORATION COMMISSION
 2/8/82
 FEB - 8 1982
 CONSERVATION DIVISION
 WICHITA, KANSAS

Date of first production _____ Producing method (flowing, pumping, gas lift, etc.) _____ Gravity _____

RATE OF PRODUCTION PER 24 HOURS
 Oil _____ Gas _____ Water _____ Gas-oil ratio _____
 bbls. MCF % bbls. CFPB

Disposition of gas (vented, used on lease or sold) _____ Perforations _____

**The person who can be reached by phone regarding any questions concerning this information. A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum _____ Depth 150'

Estimated height of cement behind Surface Pipe all

DV USED? Yes, at 1382'

WELL LOG

Formation Description, Contents, etc.	Top	Bottom	Name	Depth
	0'	24'		
	24'	255'		
sand and shale	255'	511'		
sand and shale	511'	1444'		
anhydrite	1444'	1477'		
anhydrite	1477'	1486'		
shales and limes	1486'	1990'		
shale and lime	1990'	2151'		
shale and lime	2151'	2161'		
sand and shale	2161'	2350'		
shale and lime	2350'	2577'		
shales and lime	2577'	2751'		
lime and shale	2751'	2979'	Topeka	2968'
shale and lime	2979'	3119'		
lime and shale	3119'	3239'	Heebner	3175'
shale and lime	3239'	3309'	Toronto	3199'
shale and lime	3309'	3383'	Lansing/KC	3216'
lime and shale	3383'	3448'	Base/KC	3429'
lime and shale	3448'	3510'	Arbuckle	3465'
arbuckle	3510'	3553'		
arbuckle	3553'	3619'		
	3619'	RTD		

A F F I D A V I T

STATE OF KANSAS, COUNTY OF ROOKS SS, _____

Charles G. Comeau OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS Secretary-Treasurer (FOR)(OF) LIBERTY ENTERPRISES, INC.


OPERATOR OF THE McClellan LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 2 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 27th DAY OF November, 19 81, AND THAT


ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) 

 Charles G. Comeau

SUBSCRIBED AND SWORN BEFORE ME THIS 5th DAY OF February 19 82


 SHARON GARVERT
 NOTARY PUBLIC
 STATE OF KANSAS
 My Appt. Expires 10-24-84

Sharon Garvert

 NOTARY PUBLIC
 Sharon Garvert

MY COMMISSION EXPIRES: _____