

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 16 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clark of Southwest Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Clark guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Cox Well No. B-1

Location: NW-SW-NE Sec. 26 Twp. 9 Rge. (E)(W) 21

County: Graham Total Depth 3818 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Clark was instructed to plug the well as follows:

187'--8 5/8" Surface casing, cement circulated.

3816'--5 1/2" Production casing cemented on bottom with 100 Sx. Open hole completion. 5 1/2" Has been squeezed in Dakota break-in.

Sand well back to 3800' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 15 sacks gel and 130 Sx. cement.

Very truly yours,

W. L. Daniels
 Conservation Division Agent