

State of Kansas



FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission
CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
3/2/64
MAR 2 1964

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Albert Unruh of Southwest Csg. Pulling Co. has this date requested permission to plug the following described well:
Herman Geo. Kaiser, Oil Producer
Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Herman George Kaiser Oil Producer,
Complete Address: 909 Palace Building, Tulsa, Oklahoma.
Lease Name: Bragg Well No. 4
Location: SW-SE-NE Sec. 33 Twp. 9 Rge. (E) (W) 21
County Graham Total Depth 3880 Oil Well X
Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:
223' -- 8 5/8" Surface pipe, cement circulated with 135 Sx.
3875' -- 5 1/2" Production casing cemented with 125 Sx.

Sand well back to 3870' and set 5 Sx. cement with dump bailer.
Pull 5 1/2" casing to 600' and circulate heavy gel mud. Pull 5 1/2" casing to 540' and displace 20 Sx cement thru 5 1/2". Pull 5 1/2" to 225' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2", set bridge @ 35' and 10 Sx. cement to bottom of cellar.

Very truly yours,
N. L. Nichols