

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 5/27/63
 MAY 27 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Walter Voth of Knight Casing Pulling Co., has this

date requested permission to plug the following described well:
American Petrofina Co. of Texas

Mr. Voth guarantees payment of the plugging fee.

Operator's full Name: American Petrofina Company of Texas,

Complete Address: Box #209, Russell, Kansas.

Lease Name: Cox Well No. 5

Location: NW-NW-NW Sec. 33 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3903 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Voth was instructed to plug the well as follows:

255'--3 5/8" surface pipe, cement circulated with 150 Sx.

3900'--5 1/2" cemented with 75 Sx on bottom & 500 Sx thru DV

tool @ 1600'. Top of cement @ 650' (Temp. Survey).

~~RMKXXX~~ Sand well back to 3890' and set 5 Sx cement with dump bailer.

Pull 5 1/2" to 600', circulate heavy gel mud and displace 20 Sx

cement thru 5 1/2". Pull casing to 250' and displace 20 Sx cement
thru 5 1/2". Pull casing set plug @ 35' and 10 Sx cement to bottom
of cellar.

Very truly yours,

W. L. Nichols
 Conservation Division Agent