

State of Kansas



15-065-19003-00-01

State Corporation Commission

CONSERVATION DIVISION

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Rhyne of Ralph R. Rhyne, has this
date requested permission to plug the following described well:

Mr. Rhyne guarantees payment of the plugging fee.

Operator's full Name: Ralph R. Rhyne,

Complete Address: Box #385, Russell, Kansas.

Lease Name: Cox Well No. 6 SWD

Location: SW-NE-NW Sec. 33 Twp. 9 Rge. (E)(W) 21

County Graham Total Depth 4304 Oil Well

Gas Well Input Well SWD Well X D & A Lost Hole

Mr. Rhyne was instructed to plug the well as follows:

230'--8 5/8" Surface pipe, cement circulated with 150 Sx.
3935'--5 1/2" casing cemented with 200 Sx. on bottom, DV tool set @ 1790'
with 400 Sx. cement circulated.

Sand well back to 3900' and set 5 Sx. cement with dump bailer. Push
plug to 1550', sand back to 1500' and set 5 Sx. cement with dump bailer.

Let cement set, bail hole dry and fill to cellar with Redi-Mix cement.

Very truly yours,

A. L. Nichols

Conservation Division Agent

9/15/67
SEP 15 1967
CONSERVATION DIVISION
Wichita, Kansas