

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian

WICHITA, KANSAS 67217

RECEIVED
STATE CORPORATION COMMISSION11/4/74
NOV 4 1974CONSERVATION DIVISION
Wichita, KansasVERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ernie Doty of Pipe Pullers, Incorporated, has this date requested permission to plug the following described well:

Mr. Doty guarantees payment of the plugging fee.

Operator's full Name: C & G Drilling Company,

Complete Address: 1107 Union National Bank Bldg., Wichita, Kansas.

Lease Name: DeYoung Well No. 1

Location: SW*SW*SW Sec 35 Twp. 9 Rge. (E)(W) 21

County: Graham Total Depth 3834' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Doty was instructed to plug the well as follows:

234'--8 5/8" Surface casing, cement circulated with 150 Sx.
3831'--5 1/2" Production casing, cemented on bottom with 100 Sx. (Open hole completion).

Sand well back to 3815' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 25 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

M. L. Nichols
Conservation Division Agent